



“औद्योगिक, पर्यटकीय र हरित नगर, स्वच्छ, सुरक्षित र समृद्ध नगर”

# दमक नगरपालिका नगर कार्यपालिकाको कार्यालय

दमक, झापा  
कोशी प्रदेश, नेपाल



फोन: ०२२-५८००४४, ५८०१३०, ५८०५२२  
www.damakmun.gov.np  
info@damakmun.gov.np

प.सं.: ०८२/८३/योजना

च.नं. २१४१



मिति: २०८२/०८/१५

## विषय: दररेट पेश गर्ने सम्बन्धमा ।

श्री सूचीकृत निर्माण व्यवसायी फर्म/कम्पनीहरू ।

प्रस्तुत विषयमा दमक नगरपालिकाको कार्यालय परिसर भित्र विद्युत उपशाखा कक्ष तथा भण्डार कक्ष निर्माण गर्नका लागि इच्छुक निर्माण व्यवसायी फर्म/ कम्पनीहरूले यसैसाथ संलग्न BOQ भरी मिति २०८२/०८/१९ गते दिनको १:०० बजेभित्र निवेदन सहित पेश गर्नुहुन जानकारीका लागि यो सूचना प्रकाशित गरिएको छ ।

निवेदनसाथ पेश गर्नुपर्ने कागजातहरू:

- १) फर्म / कम्पनी रजिस्ट्रेसन प्रमाणपत्रको प्रतिलिपी
- २) आ.व. ०८१/८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपी वा Time Extension को प्रमाण ।
- ३) आ.व. ०८२/८३ सम्मको नवीकरण भएको निर्माण इजाजत पत्रको प्रतिलिपी ।
- ४) भ्याट दर्ता प्रमाणपत्रको प्रतिलिपी ।

*Sunil Niroula*  
२०८२/०८/१५  
सुनिल निरौला  
प्रमुख प्रशासकीय अधिकृत

**Damak Municipality**  
**Office of the Municipal Executive**  
**Damak, Jhapa**  
**Koshi Province, Nepal**

**QUANTITY & ABSTRACT OF COST ESTIMATE**

बायोोजनाको नाम : दमक बफिसको स्टोर तथा ईलेक्टिक शाखा निर्माण

स्थान : दमक १

S.N.	Description of work	Unit	Quantity	Rate (NRs)	Amount (NRs)
1.0	Site, Drain Clearence, Diversion, Dewatering, Rehabilitation & Dismantling old structures & disposal, Hoding Board and Miscellaneous Works .	Jobs.	1.00		
2.0	Earth works in Excavation by me including back filling the trench in hard or GBM soil complete works .	Cu.m	2.33		
3.0	sand/gravel filling Ground with good quality Gravel sprinkling water, ramming & consolidating with all complete.	cum	4.93		
4.0	Plain cement concrete work (1:2:4) and foundation work with cement, sand & crushed aggregate of 10 mm to 38 mm gauge including mixing with mixture machine and compaction by vibrator, laying in line and level with curing all types of works as per specification and instruction of site engineer	Cu.m	4.29		
5.0	Providing and laying brickwork in (1:4) super structure with approved quality first class chimney made brick in perfect line and level, finished including wetting the bricks, packing the joints and curing the work and necessary scaffolding, complete in all types and thickness of walls, columns, etc. as per drawings, specification and instruction of engineer	Cu.m	10.42		
6.0	cement sand mortar plaster in (1:4) work on wall surface with proper curing all complete work	sq.m.	161.20		
7.0	Plain cement concrete M20 for R.C.C work with cement, sand & crushed aggregate of 10mm to 38 mm gauge including mixing with mixture machine & compaction by vibrator, laying in line and level with curing the job in all types of R. C. C works complete as per specification & instruction by the Engineer.	Cu.m	2.80		
8.0	Tor/TMT Reinforcement work for RCC work including supply, straighting, cutting, binding and laying of different diameter steel rod in all types of RCC work as per design, drawing, specification and instruction of engineer	KG	132.25		
9.0	Centring & shuttering works with local Hardwood including plastic sheet & nails complete works(Form Works)	sqm	11.22		
10.0	Weather coat (Apex) paint, Two coat over one coat primer of approved colour and shade as per specification and instruction all complete	m2	192.00		
11.0	(25x 25 x3)Equal angle frame, 7 mm dia. Steel rod mesh @ 100 mm C/C gap , 3 x 20 Ms @ 150 C/C. Mesh making, Fitting & fixing All complete	sqm	4.50		
12.0	Supplying , fitting and Welding squire iron pipe all complete with one prime Coat as per approved drawing ,specification and instruction of site engineer.	kg	60.00		

<b>13.0</b>	CGI Sheet With fitting all complete work as per site engineer	<b>sqm</b>	6.40		
<b>14.0</b>	Aluminium Framed Casement door one way openable with Naturally Anodized Colour in the Section of 88x45 x1.5 mm including 5 mm thick Glass (excluding the cost of handle).	<b>sqm</b>	3.90		
<b>15.0</b>	Aluminium Framed Fixed Partition with Anodized Colour in the Section of 101 x 45 x 1.5 mm including 5 mm thick Glass or Board 9mm Laminated with one side openable Door.	<b>sqm</b>	4.50		
<b>16.0</b>	Providing & Laying of interlocking type of approved & pattern over 80mm thick stone dust including compaction, dust laying of interlocking paving blocks with line & level all complete as per draing & instruction Engineer	<b>sqm</b>	294.02		
<b>17.0</b>	Electric Works	<b>ls</b>	1.00		
	13% vat				
	Total Amount				